



| | | |
|--------------------|---|--------------------------|
| Materials/Finishes | Zinc Plated Carbon Steel (8500Z) | T-304 Stainless (8500SS) |
| | T-316 Stainless (8500SS) | |
| Variants: | N/A | |
| Service: | Designed to steady a horizontal run of pipe against a perpendicular section of strut. | |
| Approvals: | N/A | |
| Ordering: | Specify figure number, finish and pipe size. | |
| Notes: | Item numbers specify OD Size. See chart for IPS and CTS equivalent. Thermoplastic insulating liner. | |

| OD PIPE SIZE | IRON PIPE SIZE | COPPER TUBE SIZE | WGT EACH (LBS) |
|--------------|----------------|------------------|----------------|
| 1/4 | - | 1/8 | 0.110 |
| 3/8 | 1/8 | 1/4 | 0.110 |
| 1/2 | 1/4 | 3/8 | 0.110 |
| 5/8 | 3/8 | 1/2 | 0.120 |
| 3/4 | - | 5/8 | 0.130 |
| 7/8 | 1/2 | 3/4 | 0.200 |
| 1 | 3/4 | - | 0.210 |
| 1-1/8 | - | 1 | 0.275 |
| 1-1/4 | - | - | 0.292 |
| 1-3/8 | 1 | 1-1/4 | 0.310 |
| 1-1/2 | - | - | 0.354 |
| 1-5/8 | 1-1/4 | 1-1/2 | 0.400 |
| 1-3/4 | - | - | 0.413 |
| 1-7/8 | 1-1/2 | - | 0.425 |
| 2 | - | - | 0.454 |
| 2-1/8 | - | 2 | 0.483 |
| 2-3/8 | 2 | - | 0.600 |
| 2-5/8 | - | 2-1/2 | 0.610 |
| 2-7/8 | 2-1/2 | - | 0.650 |
| 3-1/8 | - | 3 | 0.630 |
| 3-1/2 | 3 | - | 0.770 |
| 4 | 3-1/2 | - | 1.022 |
| 4-1/8 | - | 4 | 0.900 |
| 4-1/2 | 4 | - | 1.100 |
| 5-5/8 | 5 | - | 1.300 |
| 6-1/8 | - | 6 | 1.300 |
| 6-5/8 | 6 | - | 1.400 |

| PROJECT INFORMATION | | | APPROVAL STAMP |
|---------------------|-------------------|--------------|----------------|
| Project: | | Notes: | |
| Address: | | | |
| Contractor: | | | |
| Engineer: | | | |
| Date: | | | |
| Approved | Approved as Noted | Not Approved | |